WATER SUPPLY DIVISION, BANGALORE.

Notification dated 24th August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, up to 13th September 1929 till 3 P.M., for laying 6" Cast Iron Main in Narayana Sastry Road by branching 12" Cast Iron Main and sinking with 4" Cast Iron Main in Pindarageri Road, Mysore to improve Water Supply to Chamundi Extension and Old Wood Yard, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Water Supply Division, between the hours of 11 A.M. to 5 P.M., office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 65 only, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Laying 6" Cast Iron Main in Narayana Sastry Road by branching 12" Cast Iron Main and linking with 4" Cast Iron Main in Pindarageri Road, Mysore to improve Water Supply to Chamundi Extension and Old Wood Yard, Mysore, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate of quantities for laying 6" Cast Iron Main in Narayana Sastry Road by branching 12" Cast Iron Main and linking with 4" Cast Iron Main in Pindarageri Road, Mysore, to improve Water Supply to Chamundi Extension and Old Wood Yard, Mysore.

No.	Items of work	Per	Quantity
	LABOUR.		
1	Earthwork excavation, refilling and Tamping 1485 x 4 x 4, 10 x 5 x 8, 10 x 4 x 4, Total C.ft. 24,320, C.yd. 901.	Cyd.	901
2	Fixing branches 3"x 6"	No.	1
3	Do 12"x 6"	,,	1
4	Do 12" sluice valve	,,	1
5	Do 6" do	,,	1
6	Fixing 3" sluice valve	,,	1
7	12" cast iron cuts	,,	4
8	6" do	,,	2
9	3" do	,,	4
10	12" lead joints	,,	6
11	6" do	,,	165
12	3" do	,,	4
13	4" cast iron cuts	,,	5
14	4" lead joints	,,	5
15	Constructing valve cistern 4'x 6'x 4'	,,	1
16	Do 4'x 4'x 7'	,,	1
17	Do 3'x 3'x 4'	,,	1
18	Laying and jointing 6" cast iron pipe	Cwt.	412½

M. L. NARASIMAIENGAR,
For *Executive Engineer.*

BANGALORE DIVISION.

Notice dated 15th—22nd August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 7th September 1929 for Restoring Hanicandee Anikut